

**UNIVERSITI TEKNOLOGI BRUNEI  
NEGARA BRUNEI DARUSSALAM**


**TARIKH TUTUP/  
CLOSING DATE: 18 DISEMBER 2018 2.00 PETANG**

**BIL. SEBUTHARGA/  
QUOTATION NO: UTB/QTN/2018-2019/15/EST  
TARIKH/DATE: 05 DISEMBER 2018**

**NOTA:  
SILA HANTAR SEBUT HARGA TERUS  
KEPADA:  
BAHAGIAN KEWANGAN  
1F.32, TKT 1, BLOK F,  
UNIVERSITI TEKNOLOGI BRUNEI  
LEBUHRAYA TUNGKU  
GADONG BE1410  
NEGARA BRUNEI DARUSSALAM**

**TAJUK SEBUTHARGA/QUOTATION TITLE:  
URGENT WORKS FOR ANTI-TERMITE TO BLOCK A AND BLOCK D,  
UNIVERSITI TEKNOLOGI BRUNEI**

Nama/Name : \_\_\_\_\_  
Jawatan/Designation : \_\_\_\_\_  
Telepon/Telephone : \_\_\_\_\_  
Tandatangan/Signature : \_\_\_\_\_  
Tarikh/Date : \_\_\_\_\_



**COP RASMI SYARIKAT  
COMPANY'S STAMP**

**QUOTATION TITLE: URGENT WORKS FOR ANTI-TERMITE TO BLOCK A AND BLOCK D,  
UNIVERSITI TEKNOLOGI BRUNEI, NEGARA BRUNEI DARUSSALAM.**

**QUOTATION NO: UTB/QTN/2018-2019/15/EST**

- A. All quantities are provisional and subjected to final measurement upon completion.  
 B. The S.O. will not entertain any claims if this is not formalised for any approved variation.

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE B\$	AMOUNT B\$
	<p><b>Provide all labour, materials, tools, equipment and transport for the proper execution of the following works to its working condition and as directed by S.O to S.O satisfaction. Rate shall include to make good all works disturbed to match existing or as directed by S.O and remove debris to contractor's own dumping yard.</b></p> <p>1. Block A; Approx Area: 2400 sq.m                      2. Block D; Approx Area: 1800.00 sq.m                      ❖ <b>Total Area : 4200.00 sq.m</b></p>				
<b>1.0</b>	<b>METHOD 1</b>				
1.1	<p>Drill neat hole of 13 mm – 15 mm diameter of 300 mm – 400 mm center along both side of and at 50 mm – 100 mm away from interior and exterior walls / built in cabinet through concrete floor or apron, at 450 mm deep so as to reach the soil and inject at least 5 litres of the dilute Premises 200 SC termiticide per holes or approved equivalent in accordance with the manufacturer recommendation using low pressure pump 15 – 25 psi.</p> <p><b>Approx Area : 4200.00 m<sup>2</sup></b></p>	L.S.	L.S.		
<b>2.0</b>	<b>METHOD 2</b>				
2.1	<p>Make holes and inject fine termiticide dusts into all termite galleries or tunnels of all timber frames, fixtures, timber skirting, floor board, timber partition, built in cabinets and wardrobes, ceiling boards and roof timber and sealed with appropriate materials upon completion.</p> <p><b>Approx Area : 4200.00 m<sup>2</sup></b></p>	L.S.	L.S.		
2.2	<p>Brush on or spray with dilute Premise 200 SC termiticide in accordance with the manufacturer's recommendation into all termites galleries or tunnels that are visible on the expose parts of timber fixtures floor skirting, built in cabinet, ceiling boards and roof timber.</p> <p><b>Approx Area : 4200.00 m<sup>2</sup></b></p>	L.S.	L.S.		
<b>SUB-TOTAL CARRIED FORWARD</b>					

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
<b>SUB -TOTAL BROUGHT FORWARD</b>					
<b>3.0</b>	<b>OTHER</b>				
3.1	External inspection and treatment for trees, logs, stumps, poles and any timber materials within the compound of the infested premises are found defected and suspected of harbouring termites shall be probed and appropriate treatment measures should be taken if found to be infested, dispose off site any soil or back fill with imported soil any holes occur due to the treatment.	L.S.	L.S.		
3.2	<p>Supply and install new engrave aluminium sheet <b>size 200 mm x 150 mm</b> stating as below :</p> <div style="border: 1px solid black; padding: 5px; margin: 10px 0;"> <p><b>Anti Termite Treatment Carried Out By :</b></p> <p><b>Completion On :</b></p> <p><b>Expired Date :</b></p> </div> <p>Location to be fixed on the wall as directed by the S.O.</p> <p><b>NOTE:</b></p> <ul style="list-style-type: none"> <li>▪ <b>Contractor is advised to visit the site prior to quoting price.</b> <b>( Locations map and areas to be treated is as per attached)</b></li> <li>▪ <b>All items are provisional.</b></li> <li>▪ <b>Termite Treatment shall come with 5 years Warranty Period &amp; Contract shall submit the Warranty upon completion of this contract.</b></li> <li>▪ <b>Contractor shall make Routine Post Inspection every six months with in Warranty period and shall submit schedule of inspection upon completion this contract.</b></li> <li>▪ <b>Payment only will be release after complying of the above requirement.</b></li> </ul>	No	2		
<b>GRAND TOTAL CARRIED TO QUOTATION FORM</b>					

-----  
 Cop Rasmi Syarikat dan Tandatangan  
 Company's Stamp and Initial

<b>Tempoh Sahlaku Sebutharga/<i>Quotation Validity</i></b>	<b>:</b>	<b>Six (6) months</b>
<b>Tempoh Penghantaran/<i>Delivery Period</i></b>	<b>:</b>	
<b>Tempoh Pemasangan/<i>Implementation Period</i></b>	<b>:</b>	
<b>Waranti/Warranty</b>	<b>:</b>	
<b>Penyelenggaraan (Jika ada)/<i>Maintenance (If Any)</i></b>	<b>:</b>	

FOR REVIEW ONLY

FOR REVIEW ONLY