

RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION

Tajuk / Title : PROPOSED NEW REINFORCED CONCRETE BASE FOR BSP DONATED BEAM PUMP / NODDING DONKEY ' OIL PUMP RIGS.

Bil. Sebutharga /
Quotation Reference No.:
UTB/OTN/2019-
2020/01/EST

Ruj. Permohonan /
Request Reference:

No. UTB /
UTB No.:

	Keterangan / Description	Kuantiti Quantity	Unit Unit	Kadar Rate	Jumlah Amount
	<p><u>GENERAL NOTE</u></p> <p>Rate to include supply all necessary workforce, supervision, plan, tools, vehicle and etc. for the successful and timely completion of the following works. Submission of two sets of photographs before and after completion of the works.</p> <ol style="list-style-type: none"> 1) Contractors are to clean up and remove all debris off site or rooms at their own expenses. 2) Contractor to provide an electrical generator and water tank for temporary supply. 3) Contractor is advised to do a site or building visit before submitting the quotation. 4) Contractors are to protect the occupant's properties. 				
01-	<p><u>PRELIMINARIES</u></p> <p>Contractor to comply with the current occupational safety and health under MOD.</p>	L.S			
A	<p>Occupational Safety and Health</p> <ol style="list-style-type: none"> a. Personal Protective Equipment (Clause 1.7) b. Site Safety Signage (Clause 1.13) c. Prevention of Fall of Workplace (Clause 3.14) d. Ladders (Clause 3.4) e. Any other Clauses related to this Contract 				
B	<p>Electrical (Clause 4)</p>				
JUMLAH DIBAWA KE DEPAN AMOUNT CARRIED FORWARD					

RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION

Tajuk / Title : PROPOSED NEW REINFORCED CONCRETE BASE FOR BSP DONATED BEAM PUMP / NODDING DONKEY ' OIL PUMP RIGS.

Bil. Sebutharga /
Quotation Reference No.:
UTB/OTN/2019-
2020/01/EST

Ruj. Permohonan /
Request Reference:

No. UTB /
UTB No.:

Bil. No.	Keterangan / Description	Kuantiti Quantity	Unit Unit	Kadar Rate	Jumlah Amount
02-	REINFORCED CONCRETE BASE To construct new reinforced concrete base detail as below : a- Size of base 1 : 4.5m L x 2.5 m W x 0.8m D. b- Size of base 2 : 1.5m L x 1.75 m W x 0.8m D. c- Size of the signage board base : 0.6m L x 0.6m W x 0.6m D. d- The R.C. base is to be of smooth plastered with heavy duty external industrial paint finished.	 1 1 1 1			
03-	STRUCTURAL DESIGN The participated contractor is required to submit : a- A soil investigation report of the proposed site location area. b- The structural drawing shown is only a proposal and can be used for construction purpose but it should be first clearly certified by the registered approved MOD consultants. c- Optionally the appointed contractor can also submit their own structural design drawing and certified by the registered approved MOD consultants. d- The advised concrete strength to be used : Grade 35. e- The approximate weight of the noddling donkey 'oil pump rigs : 6 to 15 tons.				
JUMLAH KESULURUHAN BAGI RINGKASAN SEBUTHARGA INI TOTAL AMOUNT FOR THIS SUMMARY OF QUOTATION					

RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION

Tajuk / Title : PROPOSED NEW REINFORCED CONCRETE BASE FOR BSP DONATED BEAM PUMP / NODDING DONKEY ' OIL PUMP RIGS.

Bil. Sebutharga /
UTB/QTN/2019-2020/01/EST

Quotation Reference No.:

Bil. No.	Keterangan / Description	Kuantiti Quantity	Unit Unit	Kadar Rate	Jumlah Amount
04-	<p>f- To used R.C. / Steel tubular or equivalent strength pile to be piled until set finish ground. The pile size and quantity shall be advised and decided by the appointed structural engineer.</p> <p>g- To used T 25 steel bars for all pile cap steel members at a spacing of 300 c/c.</p> <p>VISITORS INFORMATION SIGNAGE BOARD.</p> <p>To supply and install a new visitors information free standing heavy duty weather proof sign board. The contractor is required to submit the proposal design as advised by the project architect.</p>	1			
05-	<p>PAINTINGS.</p> <p>a- To clean and water jet the nodding donkey ` structure before to apply the new paint primer and finishing coats.</p> <p>b- To paint the new concrete base and nodding donkey ` structure with heavy duty weather proof marine paint finished or equivalent as approved by the project architect.</p>	L.S			
<p style="text-align: center;">JUMLAH KESULURUHAN BAGI RINGKASAN SEBUTHARGA INI TOTAL AMOUNT FOR THIS SUMMARY OF QUOTATION</p>					

RINGKASAN SEBUTHARGA
SUMMARY OF QUOTATION

Tajuk / Title : PROPOSED NEW REINFORCED CONCRETE BASE FOR BSP DONATED BEAM PUMP / NODDING DONKEY ' OIL PUMP RIGS

Bil. Sebutharga /
Quotation Reference No.:
UTB/OTN/2019-
2020/01/EST

Ruj. Permohonan /
Request Reference:

No. UTB /
UTB No.:

Bil. No.	Keterangan / Description	Kuantiti Quantity	Unit Unit	Kadar Rate	Jumlah Amount
06-	<p>NOTES :.</p> <p>a- The transfer mobilization of the nodding donkey structure from BSP Seria to the project site will be borne by the BSP contractor.</p> <p>b- The appointed contractor is required to prepare an assistance during process of transfer and unloading of the structural nodding donkey ' oil rigs to the site.</p> <p>c- The appointed contractor is advised to meet the project architect for early consultation and clear briefing on the process of works to be carried out.</p>				
<p style="text-align: center;">JUMLAH KESULURUHAN BAGI RINGKASAN SEBUTHARGA INI TOTAL AMOUNT FOR THIS SUMMARY OF QUOTATION</p>					